CHITALDRUG DIVISION.

Dated 24th January 1923.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 28th February 1923, for constructing a High School at Davangere.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1925.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes as earnest money, and be superscribed tender for constructing a High School at Davangere, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer for Roads and Buildings, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items of work	Units	Quantities
1	Earthwork, excavation and filling in basement	C. ft.	19,775
2	Concrete in chunam	"	3,838
3	Burnt or trap stone in mortar	"	13,468
4	Burnt brick in mortar	"	25,272
5	Do arch work	"	5,368
6	Burnt stone slabs 6" thick, dressed	S. ft.	2,516
7	Teakwood doors pannelled with all iron fittings, complete	"	682
8	Teakwood windows with glazed shutters inside and venitioned shutters outside and with iron bars and fittings, etc., complete.	"	780
9	Teakwood semi-circular fan lights over doors and windows with glazed shutters and accessories, complete.	"	726
9A	Teakwood ventilators with glazed shutters, complete	"	283
10	Teakwood wall shelves with pannelled shutters and planks, etc., complete ..	"	240
11	5" x 12" rolled steel girders including painting and hoisting and fixing, etc., complete	R. ft.	36
12	Teakwood wrought and put up including wood oiling	C. ft.	1,009
13	Teakwood king post trusses with iron fittings and wood oiling and hoisting, etc., complete.	Each	20
14	Cut stone posts including nice base and capital	"	30
15	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete	Sqr.	124·20
16	Ornamental ridge tiles set in mortar	R. ft.	410
17	Pucca terrace with brick on edge 9" thick, complete	Sqr.	3·55
18	Ornamental parapet 2' high including pedestal	R. ft.	130
19	Ornamental dental cornice 9" x 9" including string course	"	1,028
20	Ornamental cornice over doors and windows 4½" x 4½" with pendents and key ..	"	2,348
21	Binding wall over gables ends	"	269
22	Masonry finials ornamental, big	Each	19
23	Flower finial over pillasters, front	"	22
24	Ornamental stay adjoining passage parapet	"	4
25	Gable ornaments with double headed eagle and scroll, etc.	"	8
26	Gable ornament over passage with scrolls	"	1
27	Ornamental panels in entrance with scrolls	"	8
28	Do arch work with key	"	2
29	Teakwood gate with iron parts, etc., complete	"	1
30	Teakwood ornamental gate with iron parts, etc., complete for front passage ..	"	1
31	Teakwood ornamental cave boards 9" x 1" with wood oiling, complete	R. ft.	277
32	Teakwood ornamental large board including finials and pendents	Each	4
33	Coping with burnt brick in chunam including plastering, etc., complete	R. ft.	167
34	Flooring with 2" thick Cuddappa slabs over 3" concrete bed including cement pointing	Sqr.	7·663
35	Chunam plastering	"	316·14
36	White washing inside and colourwashing outside, two coats]	"	316·14
37	Silicate painting to doors and windows	"	49·26
38	Painting with chunam	"	2·080
39	Dormer windows including, masonry, wood work, and roofing, etc., complete ..	Each	6
40	Brackets below big windows	"	40
41	Panels between brackets below big and small windows	"	260
42	Zinc sheeting to vallies including planking, etc., complete	Sq. ft.	1,101
43	Drainage pipe C. I.	R. ft.	40
44	Teakwood screen, complete	S. ft.	160

S. A. RAMASWAMI IYER,
Executive Engineer.